



- NOTES:
1. CONCRETE: 4000 PSI AFTER 28 DAYS
  2. REINFORCING: 6X6/10X10 W.W.M. & FIBERS
  3. KEYED JOINT SEALED WITH BUTYL RUBBER
  4. EXCAVATION MUST BE AT LEAST 12" LONGER AND WIDER THAN TANK SIZE.

LIQUID CAPACITY (GALLONS)	TOTAL HEIGHT A	INLET INVERT HEIGHT B	WEIGHT (LBS)
1000	49"	38"	9500
1250	56"	45"	10500
1500	64"	53"	11000
2000	76"	64"	12500

**RICHARD GENEST, INC.**  
**CONCRETE**  
**LEDGE SEPTIC TANK**