



NOTES:

1. CONCRETE: 4000 PSI AFTER 28 DAYS
2. REINFORCING: 6X6/10X10 W.W.M. & FIBERS
3. KEYED JOINT SEALED WITH BUTYL RUBBER
4. EXCAVATION MUST BE AT LEAST 12" LONGER AND WIDER THAN TANK SIZE.

LIQUID CAPACITY (GALLONS)	TOTAL HEIGHT A	INLET INVERT HEIGHT B	WEIGHT (LBS)
750/250	49"	38"	9500
1000/250	56"	45"	10500
1000/500	64"	53"	11000
1500/500	76"	64"	12500

RICHARD GENEST, INC.

**TWO COMPARTMENT
SEPTIC/PUMP TANK**