



DISTRIBUTION LINE RUNNING LENGTH OF CHAMBER

- NOTES:
1. CONCRETE: 4000 PSI AFTER 28 DAYS
 2. WEIGHT PER UNIT = 2970 LBS.
 3. DESIGN LOAD 600 PSF
H-20 WHEEL LOADING AVAILABLE

RICHARD GENEST, INC.

**4X10 END MOUNT
LEACHING CHAMBER**