



JOB REQUIREMENTS:

1. WIDTH OF OPENING IN FOUNDATION WALL SHOULD BE 40" STANDARD.
2. WHEN FOUNDATION IS BACKFILLED, LEAVE MINIMUM WORK AREA, 5' OUT AT BASE, 8' OUT AT TOP, 7' WIDE.
3. BACKFILL WITH GRAVEL AND USE AN EXTERIOR FOUNDATION DRAIN AT BASE.
4. OUR TRUCK MUST BE ABLE TO GET WITHIN TEN FEET OF THE CENTER OF THE HOLE.

HOW TO ORDER:

1. MEASURE FROM YOUR FOOTING TO YOUR FINISHED GRADE LEVEL.
2. DETERMINE DIMENSION FROM PROPOSED FINISHED GRADE TO TOP OF FOUNDATION WALL.
3. REFER TO TYPES AVAILABLE AND SELECT SIZE TO ASSURE TOP OF BULKHEAD STAIRWELL WILL BE 2"-6" ABOVE FINISHED GRADE.

RICHARD GENEST, INC.

**BULK HEAD
SIZE C**