





## NOTES:

- I. WEIGHT= 13900 LBS.
- 2. CONCRETE: 5000 PSI AFTER 28 DAYS
- 3. REINFORCING: 6X6 IO/IO W.W.M. & REBAR
- 4. KEYED JOINT SEALED WITH BUTYL RUBBER
- 5. OUTLET FILTER INCLUDED WITH ALL TANKS
- 6. INLET PLASTIC BAFFLE AVAILABLE FOR NEW HAMPSHIRE
- 7. HD SEPTIC TANK TOPS ARE 6" THICK REINFORCED WITH 5/8" REBAR



1250 LOW PROFILE HD SEPTIC TANK

238 Country Club Road (Route 4) Sanford, ME 04073

(207) 324-7215 (800) 477-8177

Date: 4/2/2012