



- NOTES:
1. WEIGHT= 13100 LBS.
 2. CONCRETE: 5000 PSI AFTER 28 DAYS
 3. REINFORCING: 6X6 10/10 W.W.M. & REBAR
 4. KEYED JOINT SEALED WITH BUTYL RUBBER
 5. OUTLET FILTER INCLUDED WITH ALL TANKS
 6. INLET PLASTIC BAFFLE AVAILABLE FOR NEW HAMPSHIRE



1500 GALLON LOW PROFILE SEPTIC TANK
238 Country Club Road (Route 4) Sanford, ME 04073
(207) 324-7215 (800) 477-8177
 Date: 4/2/2012