



Item Number	Title	Mass
1	12" 375 GAL. TANK RISER	850 LBS.
2	24" 375 GAL. TANK RISER	1700 LBS.
3	36" 375 GAL. TANK RISER	2550 LBS.

- NOTES:
1. WEIGHT -SEE SCHEDULE ABOVE
  2. CONCRETE: 5000 PSI AFTER 28 DAYS
  3. REINFORCING: 6X6/10X19 W.W. FIBERS
  4. EXCAVATION MUST BE AT LEAST 12" WIDER AND LONGER THAN TANK SIZE.



**375 GALLON TANK RISER SET**  
**238 Country Club Road (Route 4) Sanford, ME 04073**  
**(207) 324-7215 (800) 477-8177**

Date: 8/12/2009