



- NOTES:
1. WEIGHT = 7100 LBS.
  2. CONCRETE: 5000 PSI AFTER 28 DAYS
  3. REINFORCING: 6X6/10X10 W.W.M. & REBAR
  4. KEYED JOINT SEALED WITH BUTYL RUBBER
  5. OUTLET FILTER INCLUDED WITH ALL TANKS
  6. INLET PLASTIC BAFFLE AVAILABLE FOR NEW HAMPSHIRE



<b>750 GALLON SEPTIC TANK</b>
<b>238 Country Club Road (Route 4) Sanford, ME 04073</b>
<b>(207) 324-7215 (800) 477-8177</b>
Date: 3/13/2010