



NOTES:

1. WEIGHT= SEE SCHEDULE AT RIGHT
2. CONCRETE: 5000 PSI AFTER 28 DAYS
3. REINFORCING RING 6X6 10/10 W.W.M. #5 BAR IN COVER
4. CAPACITY OF 420 GALLONS PLUS CAPACITY OF CRUSHED STONE BACKFILL
5. EXCAVATION MUST BE AT LEAST 12" WIDER AND LONGER THAN TANK SIZE

COMPONENT	WEIGHT (LBS.)
DRAINAGE RING	1320
78" X 4" COVER	1550
78" X 8" COVER	3100



CONCRETE DRYWELL RING 6FT DIAMETER
238 Country Club Road (Route 4) Sanford, ME 04073
(207) 324-7215 (800) 477-8177
 Date: 12/19/2011