



**NOTES:**

1. WEIGHT: 2520 LBS.
2. CONCRETE: 5000 PSI AFTER 28 DAYS
3. ALL REINFORCING TO BE #6 BARS
4. SEE SHEET "REQUIREMENTS FOR PADMOUNTED TRANSFORMER SLAB DETAILS"
5. 1 INCH PVC CONDUIT FOR GROUND GRID LEADS.
6. SEE SHEET "PAD-MOUNT EQUIPMENT GROUNDING GRID" DTR 56.223
7. EXCAVATION MUST BE AT LEAST 12" WIDER AND LONGER THAN PAD



**PSNH SINGLE PHASE TRANSFORMER PAD**

**238 Country Club Road (Route 4) Sanford, ME 04073**

**(207) 324-7215 (800) 477-8177**

**Date: 10/14/2009**