



- NOTES:
1. WEIGHT 110 LBS.
  2. CONCRETE: 5000 PSI AFTER 28 DAYS
  3. REINFORCING: 6X6 10/10 W.W.M. & FIBERS
  4. EXCAVATION MUST BE AT LEAST 12" WIDER AND LONGER THAN TANK SIZE.



## 5 OUTLET D BOX

238 Country Club Road (Route 4) Sanford, ME 04073

(207) 324-7215 (800) 477-8177

Date: 9/13/2009