





## NOTES:

- I. WEIGHT= 12300 LBS.
- 2. CONCRETE: 5000 PSI AFTER 28 DAYS
- 3. REINFORCING: 6X6 10/10 W.W.M. & REBAR
- 4. KEYED JOINT SEALED WITH BUTYL RUBBER
- 5. OUTLET FILTER INCLUDED WITH ALL TANKS
- 6. INLET PLASTIC BAFFLE AVAILABLE FOR NEW HAMPSHIRE



1250 GALLON LEDGE SEPTIC TANK

238 Country Club Road (Route 4) Sanford, ME 04073

(207) 324-7215 (800) 477-8177

Date: 6/30/2025